



San Carlo Borromeo Church, Brusio

Restoration

■ fanzun.swiss/en/referenz/kirche-san-carlo-boromeo-brusio_en/



Starting situation and idea

Widening cracks in the cupola worried the congregation. An analysis conducted by Fanzun revealed that the roof truss was incorrectly altered during renovation in the 1960s. The resulting horizontal stresses split open the external masonry.

Challenges

The slender, tall nave stood without any visible struts in the interior. The congregation and the conservation authority therefore wished to neutralise the horizontal forces in the roof truss, which was a big challenge.

Approach

After restoring the roof truss, a three-dimensional steel frame was installed to hold together the two longitudinal facades and absorb the horizontal strain. The wooden roof truss was replaced, and the façade restored. The mural in the main entrance of the church was also restored.

Developer: Kirchgemeinde, Brusio

Completion: 2001

Project type: Restoration

Project author: Fanzun AG

Construction costs: CHF 1,3 Mio

Scope of services: Cost Planning, Bids & Tenders, Construction Supervision, Cost Control, Scheduling, Quality Assurance, Development, Commissioning, Feasibility Studies, General Planning, Design, Project Management, Architecture, Civil Engineering, Guidance, Overall Supervision, Construction Management

Fanzun AG Architekten · Ingenieure · Berater

Ganzheitlich entwickeln, gestalten und realisieren.

Wir erwecken Ideen zum Leben.

Salvatorestr. 66, CH-7000 Chur
Cho d'Punt 57, CH-7503 Samedan

Center Augustin, CH-7550 Scuol
Birmensdorferstr. 108, CH-8003 Zürich

Wölflistr. 5, CH-3006 Bern
Breitfeldstr. 13, CH-9015 St. Gallen

+41 58 312 88 88
info@fanzun.swiss